

ROSCOMMON COUNTY REMONUMENTATION

923 FEB 18 1994

Dec 28 10 27 AM '93

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ROSCOMMON

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>3W</u>	<u>A - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Robert [Signature]*  
REGISTER

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 12-14-93

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - April 1839 J.Brinks Mon. - Post WIT: 8" Y.Pine S14½°W 18 lks. 9" Aspen N24°W 25 lks.	Reg. of Deeds Mon. - ½" Bar WIT: 12" W.Oak S70°E 36.60' 14" B.Oak N40°E 52.62' 12" W.Oak N50°W 61.50'	L.1, pg.115 LCRC 1982 L.Cavanagh Mon. - ½" Bar WIT: 12" W.Oak S70°E 36.60' 14" B.Oak N40°E 52.62' 12" W.Oak N50°W 61.50'
GLO - June 1852 W.Burt MON. - See above WIT: 10" Y.Pine S79°E 17 lks. 7" Aspen N36°E 22 lks.	Reg. of Deeds Nov. 1945 R.Ostling & G.Henning Mon. - ½" Bar WIT: 10" W.Oak N27°W 62.00' 6" B.Oak N37°E 53.00' 12" N.Pine S21°E 93.70'	Jan. 1991 L.Cavanagh Mon. - ½" Bar WIT: 7" R.Oak N34°W 41.35' 15" R.Oak N38°E 52.50' 12" W.Oak S79°E 36.50'
Co. Surveyor Dec. 1924 G.Delmater Mon. - Iron (fd. GLO Post & BTS) WIT: 12" Y.Pine West 37.50'		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.  
Found ½" x 30" Bar verified position by measurement to accessories of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Std. 21" x 2" Roscommon County Monument  
WIT: Spike NW side 18" R.Oak N42°E 53.12'  
Spike N side 12" W.Oak S69°E 36.61'  
Nail & tag SE face 9" Maple S52°W 12.02'  
Spike NE side 9" R.Oak N31°W 41.57'  
2" Well point N88°W 22.28'



Signed by *Marvin E. Myers* Date December 21, 1993

Surveyor's Michigan License No. 31600

Date December 14, 1993 Peer Group Approved