

**SURVEY &
REMONUMENTATION**

MAY 28 1997

9567

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in <u>ROSCOMMON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>3W</u>	<u>B-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

23 DEC 96 10:06 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Larry L. Cavanagh, in a field survey on November, 19 96
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

POST SET BY JOHN BRINK 1839
WIT: WHITE OAK 10" N46 1/2°W 26 LKS
WHITE OAK 8" N 37 1/2°E 26 LKS

FRANK J. ARLETH 1990
CERT. OF SURVEY L343, P135
NO CORNER MATERIALS NOTED
NO WITNESSES

CARL R. JOHNSON 1987
CERT. OF SURVEY
NO CORNER MATERIAL NOTED
DISTANCE NOTED
CLOSE TO MEASURED DISTANCE

FRANK J. ARLETH
CERT. OF SURVEY 1990 L349, P93
Sp. in 6" B. Oak S28°W 33.9
Sp. in 6" B. Oak S42°30'E 22.00

L.L.C.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1/2" BAR 5.5 FEET SOUTH OF SOUTH EDGE OF BLACK TOP. ALSO FOUND AND TIED IN WITNESS NAILS IN TREES
FD NAIL IN 3" B. OAK S46°E 29.31'
FD NAIL IN 6" B. OAK S39°W 37.0'
FD NAIL IN 8" W. OAK N37°W 64.65'
FD NAIL IN FENCE POST N17°E 55.15'
SEE MAP IN DOSSIER

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE NOV 17 1996**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT BRASS, STAMPED 1996 #17614
WIT: 3" B OAK S46°E 29.31'
6" B. OAK S39°W 37.0'
8" W. OAK N37°W 64.65'
FENCE POST N17°E 55.15'
CARSONITE POST SOUTH 18.05'
THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *Larry L. Cavanagh* Date NOV. 21, 1996
Surveyor's Michigan License No. 17614

LIBER 3 DOG 350