

FEB 18 1994
9236
COMMISSION

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

Dec 28 10 27 AM '93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 3W	B - 7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert J. Myers
REGISTER

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GL0 - June 1852 W.Burt Mon. - Post WIT: 5" Spruce S25°E 32 lks. 4" Spruce N79°E 32 lks.	Sept. 1954 G.Henning Mon. - ½" Bar Dec. 1924 C.Delamater Mon. - Set Cedar Post in Rd.	Jan. 1991 L.Cavanagh Mon. - Fd. ½" Bar WIT: 9" W.Oak N35°E 53.50' 14" R.Oak N35°W 49.08' 11" R.Oak N53°W 84.10' 12" R.Oak S30°E 57.42'
L.2, pg.522 Reg. of Deeds Mon. - ½" Bar	May 1940 G.Delamater Mon. - ½"x36" Bar Set Midway on line	
Nov. 1945 G. Henning & R.Ostling Mon. - ½"x36" Bar		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found ½"x18" bar over top of ½"x36" bar and accepted as the best available evidence of the position of the Original corner.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	•												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon- Set in exact location Standard 2"x21" Roscommon County Monument
Wit- Found Spike N. side 8" J. Pine S72°E 27.48
Found Spike SE side 8" J. Pine S04°W 57.10
Found Spike NE side 6" J. Pine N47°W 64.82
Found Spike NW side 10" J. Pine N40°E 52.76



Signed by Marvin E. Myers

Date DEC 21, 1993

Surveyor's Michigan License No. 31600

Date DEC 14, 1993

Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983