

FEB 18 1994
9239
COMMISSION

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 28 10 20 AM '93

For corners in

Roscommon (County)	Located in:	Corner Code #
1. Public Land Survey	T 24N R 3W	B - 9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Peer Group Approval
RECORD

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-93

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO - June 1852 W.Burt
Mon. - Post
WIT: 5" W.Oak S64°W 6 lks.
5" B.Oak N52°E 12 lks.
- L.298, pg.246 Oct. 1974 C.Ostling
Mon. - 1/2" Iron Bar
- Oct. 1990 M.E.Myers
Mon. - 1/2" Bar 15' North of C_L of Road
WIT: 1/2" Bar South 33.00'
Nail in 12" W.Oak N43°E
Nail in N. face 17" R.Oak N30°W
12" R.Oak N49°W
- L.2, pg.522 Reg. of Deeds
Mon. - 1/2" Bar
- Nov. 1981 F.Arleth
Mon. - 1/2" Bar
WIT: 10" R.Oak S34°E 57.40'
8" W.Oak N50°E 68.60'
14" R.Oak N37°W 48.50'
- Dec. 1991 L.Cavanagh
Mon. - fd. 1/2" Bar
WIT: 9" W.Oak N35°E 53.50'
14" R.Oak N35°W 49.08'
11" R.Oak N55°W 84.10'
12" R.Oak S30°E 57.42'
- L.298, pg.247 Oct. 1974 C.Ostling
Mon. - 1/2" Iron Bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2"x24" bar verified position by measurement to accessories fo record and accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon- Replaced 1/2" bar with Std. Roscommon County Monument.
- Wit- Set carsonite post 2' North of monument.
Found spike in SE side 17" R. Oak N30°W 48.98
Found 1/2" bar and cap #31600 North 33.00
Fd. spike SE face 12" W. Oak N43°E 53.33
Nail & tag in NE side 12" R. Oak N49°W 83.95
Found 1/2" bar South 33.00
Fd. Spike SW side 10" Maple S25°E 57.37
Center line of E-W Road is 15± South



Signed by Marvin E. Myers Date Dec 18, 1993
Surveyor's Michigan License No. 31600

Date Dec 7, 1993 Peer Group Approved