

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

9588

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

23 DEC 96 1:01 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in
ROSCOMMON
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------------|
| 1. Public Land Survey | T <u>24</u> N R <u>3</u> W, | <u>B-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, FRANK J. ARLETH, P.S. in a field survey on NOVEMBER 5, 1996, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1852	HENNING 1962 IN SECTION SUBD. OF SECTION 30 FOUND 1/2" BAR SET BY OSTLING.
24" Y. PINE N12°E, 10 LKS.	WIT. 7" B. OAK S60°W, 6.0'
15" Y. PINE S60°E, 42 LKS.	LARGE STONE N13°E, 77.7'
	CENTERLINE OF ROAD NORTH 51.0'
	MYERS DATE UNKNOWN FOUND 1/2" BAR NO. WIT. L, 532, P, 276.

CAVANAGH 1991
FOUND 1/2" BAR
WITS. SAME AS HENNING 1962.

CAVANAGH 1995
WIT. LARGE STONE N13°E, 77.7'
WIT. 9" B. OAK S60°W, 6.0'
WIT. 6" B. OAK S55°E, 13.52'
3/4" IRON NORTH, 51.0'

MYERS 1990 L, 584, P, 579.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR
WIT. 10" B. OAK S60°W, 6.0'
IRON IN ROAD 51.0' NORTH
LARGE STONE MOVED
6" B. OAK S55°E, 13.72' GONE

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**
DATE NOV 5 1996
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY STANDARD MONUMENT STAMPED 21266 B-11

WIT. 12" R. OAK S43°E, 61.70'
WIT. 10" W. OAK S71°E, 48.95'
WIT. 16" B. OAK S26°W, 54.00'
WIT. 10" B. OAK S60°W, 6.00'
WIT. IRON IN ROAD NORTH, 51.00'

SET CARSONITE POST AT CORNER.



Signed by *Frank J. Arleth* Date 8 Nov 96

Surveyor's Michigan License No. 21266
DATE: 3 Nov 96 PEER GROUP APPROVED.

LIBER 3 PAGE 373