

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

9238

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 28 10 28 AM '93

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 3W	C - 7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTERED

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-93

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|---|--|
| GLO - June 1852 W.Burt
Mon. - Post
WIT: 6" Maple S37°W 24 lks.
14" Aspen N40°E 26 lks. | Nov. 1945 R.Ostling & G.Henning
Mon. 1 1/2" Pipe
WIT: 24" W.Pine N02°W 52.80'
8" Y.Pine N51°E 49.80'
12" Y.Pine S52°W 27.60' | L.542, pg.355 Sept. 1985
Mon. - None Given
WIT: 24" W.Pine N02°W 52.80'
8" Norway N51°E 49.80'
12" Norway S52°W 29.60' |
| April 1903 A.E.Newman
Mon. - Set Cor.
WIT: 12" W.Pine N49 1/2°E 1.30 chs.
15" Y.Pine S69 1/2°E 1.13 chs. | Jan. 1947 C.Henning
Mon. - 1 1/2" Pipe (WHITTINGTON PARK
PLAT cor. A.E.Newman 1903)
WIT: 12" W.Pine N01°W 83 lks.
(reported as A.E.Newman's)
24"W.Pine N02°W 52.80'
(reported as Delamater's 1924)
8" Y.Pine N51°E 49.80'
12" Y.Pine S52°W 27.60' | L.513, pg.200 July 1987 F.Arleth
Mon. - None Given
WIT: None |
| Dec. 1924 G.Delamater
Mon. - Gas Pipe at Cor.
WIT: 24" W.Pine N02°W 52.80'
8" Y.Pine N51°E 49.80' | Jan. 1953 C.Henning
Mon. - 1 1/2" Iron Pipe
WIT: 24" W.Pine N02°W 52.80'
8" Y.Pine N51°E 49.80'
12" Y.Pine S52°W 27.60' | L.2, pg.522 Reg. of Deeds
Mon. - 1 1/2" Pipe
WIT: 36" W.Pine N02°W 52.80'
12" Y.Pine N51°E 49.80'
16" Y.Pine S52°W 27.60'
12" Maple S05°W 12.40'
12" Tri Maple S45°E 26.30' |
| May 1940 G.Delamater
Mon. - Gas Pipe in Cor.
WIT: 24" W.Pine N02°W 52.80'
8" Y.Pine N51°E 49.80'
12" Y.Pine S52°W 27.60' | Aug. 1941 G.Henning
Mon. - Not described | Consumers Power Co.
Mon. - 1 1/2" Pipe
WIT: 36" W.Pine N02°W 52.80'
12" Y.Pine N51°E 49.80'
16" Y.Pine S52°W 27.60'
12" Maple S05°W 12.40'
12" Tri Maple S45°E 26.30'
In S. Wheel Track |
| May 1946 R.Ostling
Mon. - 1 1/2" Pipe | L.282, pg.644 Oct. 1973
L.Cavanagh
Mon. - 1/2" Bar in 1 1/2" Pipe | |
| June 1903 L1, P33 WHITTINGTON PARK
by A.E. Newman
Mon- Heavy Cedar Post | L.296, pg.446 Aug. 1974
C.Ostling
Mon. - 1 1/2" Pipe | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
Found 1/2"x18" bar & cap #31600 over top of 1 1/2"x24" Pipe verified position by measurement to accessories and corners of record. Set in exact location Std. Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-Standard 2"x21" Roscommon County Monument
- Wit-Standard nail & Roscommon County tag in West side 14" Maple S14°W 12.49
- Found Polebarn nail & old "NET" blaze in 18" R. Pine (Norway) S57°W 27.5
- Standard nail & Roscommon County tag in SW side 11" Maple N44°W 35.85
- Found Polebarn nail SE side 17" Red Pine (NORWAY) S57°E 49.85
- Found Polebarn nail E side 14" Maple (clump) S38°E 25.80



Signed by Marvin E. Myers Date Dec 20, 1993

Surveyor's Michigan License No. 31600

Date Dec 7, 1993 Peer Group Approved