

9237 FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF ROSCOMMON  
REC 1112

DEC 28 10 28 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 3W	C - 8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Robert J. Myers*  
REGISTERED PROFESSIONAL SURVEYOR

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 12-14-93

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO - June 1852 W. Burt April 1903 A.E. Newman L.264, pg.114 June 1972 G. Henning
- Mon. - Post Mon. - Set Post Mon. 1/2" Bar & Post
- WIT: 6" Maple N57°W 14 lks. 6" Maple S70 1/2°E 49 lks. Aug. 1943 G. Henning WIT: 12" B. Oak S75°W 28.80'
- 6" Maple S70 1/2°E 49 lks. Mon. 1/2"x30" Bar Mon. 6" B. Oak N43°W 42.90'
- May 1940 C. Delmater WIT: 6" W. Birch N21 1/2°E 23.20' 6" W. Oak N22°E 23.20'
- Mon. - 1/2"x30" Bar set midway & on line 8" B. Oak N03°W 27.20' 1/2" Bar West 33.00'
- WIT: 4" R. Oak N75°W 30.10' Nov. 1945 G. Henning & R. Ostling LCRC L.1, pgs.39-40 July 1972 C. Ostling
- 14" R. Oak N24°E 76.50' Mon. - 1/2" Bar Mon. - Fd. 1/2" Bar
- Aug. 1941 G. Henning Jan. 1950 R.T. Ostling WIT: 6" W. Birch N21°30'E 23.20'
- Mon. - Not described Mon. - 1/2"x30" Bar 8" R. Oak N03°W 27.20'
- WIT: 6" W. Birch N21 1/2°E 23.20' Jan 1969 L.6, P26 LAKE VIEW ASSOCIATION by c. Ostling
- 8" R. Oak West 27.20' Mon- Not Given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 30" Bar & Cap #2240 verified by measurement to accessories of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon. - Set in exact location Std. Roscommon County Monument
- WIT: Nail & tag NE side 7" B. Oak S42°E 27.73'
- Nail & tag SE side 8" B. Oak S46°W 29.33'
- Nail & tag 13" B. Oak N37°W 43.25'
- Nail & tag 11" B. Oak n64°E 30.88'
- Fd. 1/2" bar West 33.00'
- Fd. 21" B. Oak S70°W 29.00'±



Signed by *Marvin E. Myers*

Date December 21, 1993

Surveyor's Michigan License No. 31600

Date December 14, 1993

Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER