

9233

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 28 10 27 AM '93

For corners in COMMISSION

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>3W</u>	<u>C - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - June 1852 W.Burt Mon. - Post WIT: 10" S.Pine S72°E 34 lks. 6" Aspen North 34 lks.	Nov. 1945 Henning & Ostling Mon. - 1 1/2" Pipe Sept. 1947 Henning Mon. - Not described	L.1, pg.234 LCRC Sept. 1985 L.Cavanagh Mon. - 1/2" Bar inside 1 1/2" Pipe WIT: 8" Oak S56°W 34.90' 12" Oak N37°E 38.40' 8" Maple S35°E 34.00' Top Point lg. stone N57°W 77.00'
April 1903 A.E.Newman Mon. - Set (unknown) WIT: 12" W.Pine Stump S60°W 1.28 chs. 26" W.Pine Stump S54°E 1.39 chs.	L.264, pg.114 June 1972 G.Henning Mon. - 1/2" Bar inside 1 1/2" Pipe WIT: 20" W.Pine N26°W 32.00' 20" R.Pine S25°E 29.10' 4" concrete Mon. North 33.00'	L.2, pg.522 Reg. of Deeds Mon. - 1/2" Bar inside 1 1/2" Pipe
May 1940 G.Delmater Mon. - Place 1/2"x30" Bar (fd. one GLO BT & GLO Post) WIT: Large stone N47°W 47.20' Spike 16" W.Pine N26°W 32.00' Spike 18" Y.Pine S25°E 29.10'	July 1972 Henning L.265, pg.182 Mon. - 4" Conc. Mon. WIT: Plat-Mon. North 33.00' 18" W.Oak S22°E 66.20' 14" Maple N24°W 81.20' 8" Maple N43°W 82.80'	Oct. 1990 M.E.Myers Mon. - Pipe of Record
Aug. 1943 G.Henning Mon. - 1/2"x30" Bar in 1 1/2"x14" Pipe WIT: Large stone N47°W 47.20' Spike 16" W.Pine N26°W 32.00' Spike 18" Y.Pine S25°E 29.10'	L.513, pg.16 Sept. 1985 L.L. Cavanagh Mon. - None given WIT: 8" Oak S56°W 34.90' 12" Oak N37°E 38.40' 8" Maple S35°E 34.00' Top Point lg. stone N57°W 77.00'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
Found 1/2"x34" bar inside 1 1/2"x14" pipe verified position by measurement to accessories and corners of record and accepted as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set exact location 2"x21" Standard Roscommon County Monument.
Wit-Found Concrete monument N8°E 32.94
Found Concrete monument S8°W 32.99
Set nail & tag in NE side 9" Maple S33°E 34.35
Set nail & tag in NW side 10" Maple S57°W 35.28
Set nail & tag in NW side 17" Oak N43°E 38.88
Found nail & tag S. side Maple N37°W 82.33



Signed by Marvin E. Myers Date Dec 21, 1993

Surveyor's Michigan License No. 31600

Date Dec 14, 1993

Peer Group Approved