

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

9589

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

23 DEC 96 1:01 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24</u> R <u>3</u> W	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frank J. Arleth, in a field survey on November, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

William Burt 1852
10" Y. Pine N9°W 14.1ks
14" W. Oak S67°E 26 lks
Delamater 1929
Set 1/2" bar at mid-point on line.

Henning 1955, Investigative survey indicates the existing E&W fence is in proper position for E&W 1/4 line.
Ostling: 1958
Fd. 1/2" bar

Henning 1962
1/2" bar set by Delamater used Ostling Wit.
Arleth 1990 Fd. 1/2" bar
Sp P. Pole S59°30'W 40.15 OK
12" W. Oak N62°30'W 130.8 gon
Conc Mon S55°30'E 39.65 gone

BT 8" R. Oak N61°30'W 131.3 Gone
BT 2" W. Oak N49°E 65.3 OK
BT 4" W. Oak N48°W 71.0 Gone
P. P. S59°30'W 40.15 OK
12" W. Oak N62°30'W 84.5 Gone
Con Mon. S55°30'E 39.65' Gone
Nail 8" R. Oak S55°E, 69.4 OK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" x 24" bar over 1/2" bar in Centerline of Roads E&W
Sp. in P. P.e S59°30'W 40.15'

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE NOV 8TH 1996**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set ~~Roscommon~~ County Standard Mon. Stamped 21266 C-10
N & T 12" Maple N13°W 27.90
N & T 12" W. Oak. N48°E 65.23
Nail 12" Maple Clump N43°E 46.85
Nail 10" R. Oak S35°W 60.13
Nail P. Pole S58°W 40.15
Set Carsonite Posts S58°W 39.15



Signed by *Frank J. Arleth* Date 8 Nov 96
Surveyor's Michigan License No. 21266 P. S.

DATE: 8 Nov 96 Peer Group Approved.
LIBER 3 PAGE 374