

**SURVEY &  
REMONUMENTATION**

MAY 28 1997

COMMISSION

9590

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

23 DEC 96 1:01 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in

ROSCOMMON

(County)

Located In:

Corner Code #/

1. Public Land Survey	T	<u>24</u>	N	R	<u>3</u>	W	<u>C-11</u>
	T	_____	R	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, FRANK J. ARLETH, P.S. in a field survey on NOVEMBER 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1852 SET POST WIT. 12" W. OAK S27°E, 54 LKS. WIT. 7" B. OAK S56°W, 36 LKS. 1902 PLAT OF WOODLAWN L, 1 OF PLATS P, 11. DELAMETER FOUND HOUGHTONS CORNER WIT. Y. PINE STP. S23°E, 34.50'	HENNING 1947 FOUND 3/4" PIPE IN COR. SEC. SUBD. OF 31. WIT. BT. W. PINE STP. S25°E, 34.10' WIT. BT. 8" B. OAK N51°E, 54.30' WIT. BT. 6" R. OAK N43°W, 52.60' HENNING 1962 USED IN SEC. SUBD. OF 30.	ARLETH 1990 FOUND 3/4" PIPE WIT. CONC. MON. N45°E, 47.90' WIT. 12" W. OAK N15°E, 45.80' WIT. 12" W. OAK N45°E, 68.20' WIT. SPK. IN POWER POLE N45°W, 36.65'
---	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ARLETH 1996 FOUND 3/4" PIPE OVER 1/2" BAR WIT. CONC. MON. N45°E, 47.90' WIT. SPK. 12" W. OAK N15°E, 45.80' WIT. SPK. 12" W. OAK N45°E, 68.20' WIT. SPK. POWER POLE N42°W, 36.65'	CAVANAGH 1991 FOUND 3/4" PIPE WIT. POWER POLE N39°W, 36.70' WIT. STOP SIGN POST S19°E, 37.65' WIT. 8" POPLAR S55°W, 48.0' WIT. 10" W. OAK N26°E, 45.84'
---	---

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE NOV 8 1996**

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY STANDARD MONUMENT STAMPED 21266 C-11  
WIT. CONC. MON. N45°E, 47.90'  
WIT. N&T 12" W. OAK, N15°E, 45.84'  
WIT. N&T 12" W. OAK, N45°E, 68.20'  
WIT. N&T POWER POLE N45°W, 36.65'  
WIT. N&T POWER POLE S55°W, 39.60'  
WIT. N&T 6" B. OAK, S44°E, 49.85'  
SET CARSONITE Post N45°E, 47.9' BY CONC. MON.



Signed by Frank J. Arleth Date 8 Nov 96

Surveyor's Michigan License No. 21266

DATE: 8 Nov 96

PEER GROUP APPROVED. 1 IRER 3, DATE 3 75