

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

9591

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

<u>Rosecommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>24</u> R <u>3</u> W	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

23 DEC 96 1:01 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31	0	32		33		34		35		36		
13													

I, Frank J. Arleth, in a field survey on November, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>William Burt 1852</u>	<u>Delamater 1924</u>	<u>Henning 1947</u>
18" Y. pine S27 E 54 lks	B T 4" B. Oak N17 W 34.6	1/2 corner set Mid-point
18" Y. Pine N56 W 36 lks	B T 10" W. Oak S31 W 52.0	3/4" pipe in corner
		9" B. oak S66 E 40.8
		7" B. Oak S22 W 54.3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE NOV 5th 1996

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Standard Mon. Stamped 21266 C-12
N & T 10" R. Oak West 47.33'
N & T 10" r. Oak N44 W 76.57
N & T 16" B. Oak N43 E 104.96
N & T 6" Maple S52 E 66.32
N & T B. Oak S49 W 46.80
Carsonite Post West 40.00'



Signed by Frank J. Arleth Date 8 Nov 96

Surveyor's Michigan License No. 21266 P.S.

Date: 3 Nov 96 Peer Group Approved

118ER 3 PAGE 376