

**SURVEY &
REMONUMENTATION**

9561

MAY 28 1997

**COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 3W	D - 1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

23 DEC 96 9:49 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on NOVEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO John Brink 1839 Mon.-Post WIT: 10" W.Oak N46½°W 26 lks. 8" W.Oak N37½°E 26 lks. 8" W.Pine N27°W 09 lks. 8" W.Oak N07°E 52 lks.	Survey Possible Henning Mon.-½" Bar 1' below surface 3' South of G ½" Bar to surface	F.J. Arleth Dec. 1992 L.355, pg.82 (Crawford County) Mon.-Fd. ½" Bar WIT: 8" B.Oak N30°E 57.5' 7" B.Oak N22°W 63.5' 12" B.Oak S50°W 45.0'
Aug. 1970 C.E. Ostling Mon.-None given WIT: None given	L.3, pg.173 M.E. Myers Dec. 1994 Mon.-Std. Crawford Cty. Mon. WIT: Fd. nail SW side 16" W.Pine S56°67.05' Fd. nail NW side 15" B.Oak S59½°W 45.09' Fd. nail W. side 11" Tw.W.Oak N10°E 48.51' Fd. 12" B.Oak N19°W 63.20'	Fd. carsonite post N08°E 36.57' Fd. 11" B.Oak N36°E 57.23' Fd. wit. tag & nail SE side 11" B.Oak N36°E 57.75' Fd. 3/4" ID pipe N08°E 36.57'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Crawford County monuemnt in mon. box
Found nail & tag NE 57'
Found 12" B.Oak S50°W 45.0'
Found all accessories in Liber 3, page 173 Crawford County Records
And is accepted as the best available evidence of the position of the Original Corner

ROSCOMMON COUNTY

PEER GROUP APPROVAL

DATE Nov 8th 1996

Marvin E. Myers
Marvin E. Myers, P.S.

County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon.-Std. Crawford County Mon.
WIT: Fd. nail SW side 16" W.Pine S56°E 67.05'
Fd. nail NW side 15" B.Oak S50½°W 45.09'
Fd. nail W. side 11" Tw. W.Oak N10°E 48.51'
Fd. 12" B.Oak N19°W 63.20'
Fd. 11" B.Oak N36°E 57.23'
Fd. wit. tag & anil SE side 11" B.Oak N36°E 57.75'
Fd. 3/4" ID pipe N08°E 36.57'
Fd. carsonite post N08°E 36.57'



Signed by Marvin E. Myers

Date DEC 17th 1996

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993

Liber 3 Page 200