

6833

JAN 24 1996

RECORDED  
6 OCT 95 1:48 P.M.

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in

Roscommon  
(County)

Located In:

Corner Code #

TO BE FILED IN LIBER 3 OF LAND CORNER.

- 1. Public Land Survey T 24 R 3 W E-2
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

APR 05 1996

Register of Deeds Stamp & File Number  
6 OCT 95 1:48 P.M.

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

COMMISSION

I, Frank J. Arleth, in a field survey on August, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- William Burt Henning & Ostling 1943
- Post set Fd pipe-set metal tent stake over pipe.
- S. Pine 8" S48°W 27 Sp 24" W. Pine S40°W 68.3'
- S. Pine 10" N27°E 41 Sp 14" J. Pine N32°E 83.5'
- DeLaMater 1925 Fd. well point Henning 1945 Sec. sub of sec. 4, Fd 1 1/4" pipe with tent stake to surface
- BT 12" J. Pine N32°E 53.4' Sp 24" W. Pine S40°W 68.3'
- 6" B. Oak N65°E 93.5' Sp 14" J. Pine N32°E 83.5'
- 10" B. Oak S30°W 100.4'
- N E cor. of Sovereign Park

R.C.R.C. Date unknown. 5/8"

bolt in pav't box (tent stake)

Sp. 24" W. Pine S40°W 68.3'

Sp. 14" J. pine N32°E 83.5'

1985 Fricke

Wit P. P. S60°E 35.8'

P. P. N45°E 51.34

P. P. N35°W 46.48'

Numerous Surveys of record by: Henning, Ostling, Arleth, Cavanagh and Fricke.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: August 1995 Fd. tent stake over 1 1/4" pipe in pav't bos in centerline of roads N & S and E & W
- Fd. J. Pine stump N32°E 83.5'
- Sp. in P. pole S62°E 35.8'
- Sp. in P. pole N35°W 46.48'

Accepted as the best available evidence of the position of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Roscommon County Standard Monument in pav't box - stamped E-2 T24 R3W
- N & T 10" J. Pine S31°W 56.0'
- N & T P. pole S62°E 35.85'
- N & T 14" N. pine N36°E 62.33'
- N & T P. pole N39°W 46.5'
- Carsonite Post N39°W 45.73'

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 9-8-1995



Signed by Frank J. Arleth  
Surveyor's Michigan License No. 21266 P. S.

Date 11 SEPT 95

DATE: 8 SEPT 95 PEER GROUP APPROVED

LIBER 3 PAGE 262