

6835

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon
(County)

Located In:

Corner Code #:

- 1. Public Land Survey T 24 R 3 W G-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

6 OCT 95 1:48 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

APR 05 1996

COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frank J. Arleth in a field survey on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

William Burt Henning & Ostling 1945
Set Post Fd 5/8" bar
W. Pine 18" N6°W 3.5 Wit: 12' N. Pine N16°W 58.0'
Dead pine 8" S44°E 31 10" B. Oak N58°E 57.2'

DeLaMater 1925 set Arleth 1987, Fd. 5/8" bar
5/8" x 48" bar, No Wit: 18" N. Pine N16°W 58.0'
witnesses of record. 14" B. Oak N58°E 97.2'
1/2" bar S0°25'13"W 33.0'

Numerous surveys of record by Henning, Ostling, Cavanagh & Arleth.
R. C.R.C. Fd. 5/8" bar date unknown.
Sp. P. Pole South 30.71'
Sp. P. Pole N5°E 32.65'
Sp. 8" W. Oak S27°W 49.85'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 1995, Fd. 1" x 12" bar over 5/8" bar
Fd Wit: Sp. P. Pole South 30.71'
Sp. P. Pole N5°E 32.65'
1/2" bar S0°25'13"W 33.0'
Old N. Pine N16°W 58.0' Blown Down

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 9-8-1995

Accepted as the Best Available evidence of the position of Original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County Standard Monument in pav't box- Stamped G-3 T24N, R3W.
N & T 10" B. Oak S42°E 76.92'
Sp. P. Pole South 30.71' (old)
Sp. 8" W. Oak S27°W 49.85' (old)
N & T 18" W. Oak N32°W 38.32'
Sp P. Pole N5°E 32.65' (old)
N& T 12" R. Oak N17°E 57.84'
Carsonite Post S27°W 36.0'



Signed by Frank J. Arleth
Surveyor's Michigan License No. 21266 P.S.

Date 11 SEPT 95

DATE: 8 SEPT 95

PEER GROUP APPROVED

LIBER 3 PAGE 264