

6832

JAN 24 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in

Roscommon  
(County)

Located In:

Corner Code #

6 OCT 95 1:47 P.M.

- 1. Public Land Survey T 24 R 3 W G - 5
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

TO BE FILED IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

ROBERT W. SMITH  
REGISTER OF DEEDS

APR 05 1996

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

COMMISSION

I, Frank J. Arleth, in a field survey on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 William Burt 1852 Set Post S. Pine 7" S66°E 20  
 S. Pine 8" S31°W 17  
 Henning 1940 Sd. steel post in corner, No witness  
 Henning 1945 placed pipe in corner to replace steel post.  
 N.B.T. 18" W. Oak N56°15'W 41.2'  
 12" B. Oak N21°15'W 66.0'  
 R.C.R.C.  
 P. Pole S40°W 49.3'  
 P. Pole S54°E 62.2'

Plat corners for: Pinehaven as recorded in Liber 4, Page 13 and Fairhaven recorded in Liber 3 page 21.  
Arleth 1976 Fd. 1/2" bar in corner 11' North of centerline 1/2' bar S40°E 54.6'  
P.K. in P. pole N61°W 33.25'  
P. K. P. Pole N51°E 31.75'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 August 1995 Found 1/2" bar in corner, Corner is 4' East of centerline of road South and 11' North of centerline East & West Road.  
 Fd. P.K. in P. pole N61°W 33.25'  
 P.k. in P. Pole N51°E 31.75'

Accepted as the Best available evidence of the position of original corner.

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 9-8-1995 *MEH*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set Roscommon County Standard Monument in Pav't box - Corner stamped G-5, T24N, R3W 21266  
 N & T 16" W. Oak S22°E 73.22'  
 N & T 18" R. Oak S47°W 83.31'  
 N & T 8" R. Pine N51°W 50.79'  
 P.K. in P. Pole N61°W 33.25'  
 P.K. in P. Pole N51°E 31.75'  
 N & T 36" W. Oak N49°30'E 45.82'  
 Carsonite Post N56°W 36.00'



Signed by Frank J. Arleth  
Surveyor's Michigan License No. 21266 P. S.

Date 11 SEPT 95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

DATE: 8 SEPT 95

PEER GROUP APPROVED

LIBER 3 PAGE 261