

6829

JAN 24 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in  
Roscommon

(County)

Located In:

Corner Code #

6 OCT 95 1:47 P.M.

- 1. Public Land Survey T 24 R 3 W H-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

ROBERT W. SMITH  
REGISTER OF DEEDS

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

COMMISSION

I, Frank J. Arleth, in a field survey on September, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
William Burt 1852 Henning & Ostling 1944  
W. Pine 30 S39°E 42 Fd Iron & used  
B. Oak N17°W 17 Arleth 1976 Fd. 1/2" bar in  
DeLaMater 1924 Fd Old post Pav't Box  
set iron in corner Conc. Mon S45°W 46.67'  
B. T. 5" W. Oak N34°W 69.2' Conc. Mon N45°W 46.67'  
B. T. 4" W. Oak N56°E 65.9'  
B. T. 10" B. Oak N23°E 60.3'  
B. T. 12" Y. Pine S38°E 81.9'

R. C. R. C. witness book  
Fd 1/2" bar in pav't box  
P. P. N45°E 36.17'  
8" Aspen S45°W 59.88'  
8" Oak S80°W 48.83'  
Plats tied to corner:  
Choctaw Woods L. 6, P. 79  
Highland Park Heights No.2 L. 7  
P. 14.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Sept. Fd. 1/2" bar in Mon box in centerline of County Road #100 & Hillsdale Road to the West. Fd. Conc. Mon. S45°W 46.67'  
B. T. 5" W. Oak N34 W 69.2'  
B. T. 12 Y. Pine S38 E 81.9'

Accepted as the best available evidence of the position of the original corner.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 9-8-1995

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set Roscommon County Standard Monument in pav't box stamped H-9 T24N, R3W. 21266  
Centerline of Road N&S and West.  
N&T in 14" R. Oak S39°W 57.63'  
N&T in P. Pole N52°E 36.55'  
N&T in 26" W. Oak N33°30'W 69.60' (old )  
N&T in 8" W. Pine S74°E 49.93'  
N&T in 26" N. Pine S38°E 81.70' (old)  
1/2" bar 33.0' East and set Carsonite Survey Post at bar.



Signed by Frank J. Arleth  
Surveyor's Michigan License No. 21266 P. S.

Date 11 SEPT 95

DATE: 8 SEPT 95 PEER GROUP APPROVED LIBER 3 PAGE 258