

**SURVEY &  
REMONUMENTATION**

MAY 28 1997

COMMISSION

9596

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in

Roscommon

(County)

Located In:

Corner Code #

23 DEC 96 1:02 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

1. Public Land Survey	T <u>24</u> R <u>3 W</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Frank J. Arleth, in a field survey on June, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- |  |  |  |
|--|--|--|
| <b>William Burt 1852</b><br>Set Post<br>18" Y. Pine N63°W 36 Lks<br>14" Y. Pine N16°E 12 Lks | <b>Ostline 1958</b><br>Found ½" bar<br>½" bar N5°43'E 33.0<br>6" B. Oak N31°W 45.8<br>6" B. Oak S62°W 66.0 | <b>Fricke 1992 Found ½" bar</b><br>10" Oak S45°W 65.7<br>8" Oak N40°W 45.6<br>½" bar South 33.0<br>Arleth 1993 (same as 1992)<br>Arleth 1994 ( Same as 1992)<br>R.C.R.C. ½" bar in Pav't Box Center-line Co. road #100<br>6" Oak N31°W 45.8<br>6" Oak S62°W 66.0 |
| <b>Delamater 1929</b><br>Set ½" bar<br>No witness  | <b>Arleth 1978</b><br>Found Pav't Box<br>N & T 10" Oak S45 W 65.7<br>N & T 8" Oak N40 W 45.6               |  |
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1996 Found ½" bar in Pav't Box in centerline of County Road #100  
Found ½" bar South 33.0  
Found ½" bar N 5 43'E 33.0  
14" R. Oak S62°W 66.0 (destroyed)  
12" R. Oak N30°W 45.8

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL**

DATE June 17, 1996  
*Marvin E. Myers*  
**Marvin E. Myers, P.S.**  
County Surveyor

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set Roscommon County Standard Monument in pav't Box Stamped 21266  
N & T 14" R. Oak S52°W 65.80  
N & T 12" R. Oak N30°W 46.12  
N & T 12" R. Oak S4°E 51.65  
N & T P. pole S61°E 69.35  
½" bar South 33.0  
½" bar N5°43'E 33.0  
Carsonite Post North 33.0



Signed by [Signature] Date June 14, 1996

Surveyor's Michigan License No. 21266 P.S.  
Date June 96 Peer Group Approved

1.168 3 PAGE 381