

**SURVEY &
REMONUMENTATION**

MAY 28 1997

9598

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

<u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
	T <u>24</u> N R <u>3</u> W	<u>I-6</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

23 DEC 96 1:02 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Frank J. Arleth, in a field survey on June, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Willaim Burt 1852	Ostling 1954	Arleth 1995
Set Post	Fd. 1/2" bar	Fd. 1/2" bar
Wit. 5" W. Pine N82°W, 42 lks.	Wit. 10" J. Pine S51°W, 39.00'	Witness same as Ostling.
Wit. 8" S. Pine S6 1/2°E, 47 lks.	Wit. 6" J. Pine N49°W, 36.90'	
DaLamater 1929	Wit. 16" W. Pine South, 72.40'	
Placed 1/2" x 48" bar Mid-Point and on line between Section Corners.	Arleth 1988	
No Witness	Fd. 1/2" bar Witness same as Ostling.	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 Found 1/2" x 48" bar
 Wit. Fd. 10" J. Pine Stp. S51°W, 39.00'
 Wit. fd. 10" J. Pine N49°W, 36.90'
 Wit. fd. 16" W. Pine South, 72.40'
 (SWAMP)

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**

DATE JUNE 17 1996

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY STANDARD MONUMENT - STAMPED - I-6 No. 21266
 Wit. N&T in 7" W. Pine N40°W, 47.44'
 Wit. N&T in 10" W. Pine S74°W, 61.15'
 Wit. N&T in 7" W. Pine S67°E, 52.55'
 Wit. N&T in 10' J. Pine N49°W, 37.20'
 Wit. N&T in 20" W. Pine South, 72.60'
 Carsonite Post set 1.0' South of Corner.



Signed by *Frank J. Arleth*
 Surveyor's Michigan License No. 21266 P.S.

Date BN 96

DATE: BN 96 PEER GROUP APPROVED / IBER 3 PAGE 38