

**SURVEY &  
REMONUMENTATION**

**APR 07 1998**

**SECTION  
9242**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970**

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

16 DEC 97 12:25 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T24N	R 3W	K-4
T	R	
T	R	
T	R	

**FILE IN LIBER 3 OF LAND CORNERS**  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey October, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838 SET POST Y. PINE 20" N18°E 53 LKS Y. PINE 20" S30°W 30 LKS	MID 1970'S L2 P 515 FD 1" IRON PIPE 34" OAK N40°E 53.5' 20" OAK S60°E 69.51' 9" OAK S40°W 42.9' 1/2" BAR NORTH 33.0'	FRANK ARLETH 21266, 1988 L537 P 416 FD PIPE 34" OAK N40°E 53.5' 20" OAK S60°E 69.51'
LARRY CAVANAGH 17614 L259 P 323, 1971 FD 1" IRON PIPE 34" OAK N40°E 53.5' 20" OAK S60°E 69.51' 9" OAK S40°W 42.9'	FRANK ARLETH 21266 1977 L334 P517 34" OAK N40°E 53.5' 20" OAK S60°E 69.51' 9" OAK S40°W 42.9'	LARRY CAVANAGH 17614 1997 FD 1" X 18" PIPE OVER 1/2" X 3" STEEL BAR AND OLD CEDAR POST 7" R. OAK N50°E 46.18' 24" R. OAK N52°W 51.07' 16" R. OAK S37°W 42.66' P. POLE SOUTH 34.9'
C EUGENE OSTLING 12026 LCRC L1 P 27, 1972 FD 1" IRON PIPE 34" OAK N40°E 53.5' 20" OAK S60°E 69.51'	FRANK ARLETH 21266 1981 L386 P655 34" OAK N40°E 53.5' 20" OAK S60°E 69.51'	

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1" X 18" PIPE OVER 1/2" X 3" STEEL BAR AND OLD CEDAR POST

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614 1997  
NAIL & TAG IN 7" R. OAK N50°E 46.18'  
NAIL & TAG IN 24" R. OAK N52°W 51.07'  
NAIL & TAG IN 16" R. OAK S37°W 42.66'  
NAIL & TAG IN P. POLE SOUTH 34.9'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Dec 5, 1997**

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh* Date Dec. 14, 1997  
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN, 1983

*LIBER 3 PAGE 41.7*