


LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

|      |     |     |
|------|-----|-----|
| T24N | R3W | L-7 |
| T    | R   |     |
| T    | R   |     |
| T    | R   |     |



FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

GLO, WILLIAM BURT 1852  
SET 1/4 SEC. POST  
S. PINE 6° N40°W 131 LKS  
S. PINE 8° N80°W 92 LKS

LCRC 1980 LI, P147  
FRANK J. ARLETH, RLS  
SET 5/8" BAR AT PROPORTIONATE  
MEASUREMENT  
SAME WITNESSES AS ABOVE

LCRC 1970S L2, P527  
NO COR MATERIAL CALLED OUT  
10' OAK N45°W 68.1'  
8' OAK N25°E 58.05'

LCRC 1995, LI, P342  
CARL F. ROSER, RLS  
FD 5/8" RE-ROD IN MON BOX  
5' J. PINE NORTH 41.35'  
5' J. PINE N31°E 50.35'  
6' J. PINE S03°W 51.88'  
16' OAK S45°W 70.20'  
DROVE 5/8" X 18" REROD W/PS CAP  
N85°57'44"E 662.12'

FRANK J. ARLETH, RLS, 1975, L308, P263  
NO COR MATERIAL CALLED OUT  
SP IN 10' OAK N45°W 68.1'  
SP IN 8' OAK N25°E 58.05'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" X 20" RE-ROD IN PAVT BOX  
FOUND FOUR WITNESSES FROM 1995  
FOUND 6' J. PINE S03°W 51.88' (NOW A STUMP)  
FOUND TWO WITNESSES FROM 1975 8' (NOW 12") OAK N25°E 58.05'  
10' (NOW 14") OAK N45°W 68.1'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3" X 21" ROSCOMMON COUNTY MONUMENT STAMPED 17614, IN PAVT BOX  
WIT: NAIL & DNR TAG IN 12" BLACK OAK S45°W 70.24'  
NAIL & DNR TAG IN 7" J. PINE NORTH 41.23'  
NAIL & DNR TAG IN 7" J. PINE N31°E 50.33'  
NAIL & TAG IN 10" BLACK OAK S32°E 76.60'  
SPIKE IN 12" OAK N25°E 58.05'  
SPIKE IN 14" OAK N45°W 68.1'  
CARSONITE POST S05°E 30.2'

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Sept 10, 1999

*Marvin E. Myers* MESA  
Marvin E. Myers, P.S.  
County Surveyor



Signed by Larry L. Cavanagh Date Sept. 14, 1999  
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983



LIBER 3 PAGE 610

SURVEY &

Mar 1 2000

SECTION