

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon
(County)

Located In:

Corner Code #

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

6 MAY 99 2:09 P.M.

ROBERT W. SMITH
 REGISTER OF DEEDS

1. Public Land Survey	T <u>24N</u> R <u>2W</u>	<u>A-4</u>
	T <u>24N</u> R <u>3W</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

To be filed in Liber 3 of Land Corners
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1838
 John Brink D.S.
 Mon. - Post
 Wit: 24" Y. Pine S45°W 5 lbs.

LCRC L. 2, P. 515
 Mon: 3/4" Pipe
 Wit: 12" Oak S30°W 56.8'
 12" Oak S41°E 32.0'

L.1, P27 LCRC C. E. Ostling, RLS #12026
 Mon - 3/4" Pipe
 Wit: 12" Oak S30°W 56.8'
 12" Oak S41°E 32.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar inside 3/4" Iron Pipe (Ostling) of record inside a monument box in the intersection of Wheeler Road N-S and Maplehurst Drive E-W. Previous witnesses were obliterated due to recent road improvements. Accepted 3/4" pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Roscommon County monument in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Roscommon County Corner in monument box.
 Wit: Set nail & tag in SE side 6" Oak N55°E 47.34'
 Set nail & tag in SW side 16" Oak S39°E 60.09'
 Nail & tag in SE side Utility Pole S46°W 36.73'
 Set Carsonite Post N35°W 45.94'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
 DATE April 19, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
 County Surveyor



Signed by *Marvin E. Myers*
 Surveyor's Michigan License No. 31800

Date April 24, 1999

LIBER 3 PAGE 593