

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon
 (County)

Located In:

Corner Code #

1. Public Land Survey T 24N R 2W
 T 24N R 3W
 T _____ R _____
 T _____ R _____
2. Property Controlling
 in Section S _____ T _____ R _____
 S _____ T _____ R _____
3. Miscellaneous
 Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A-5
M-5

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

6 MAY 99 2:09 P.M.

ROBERT W. SMITH
 REGISTER OF DEEDS

To be filed in Liber 3 of Land Corners
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1838
 John Brink D.S.
 Mon. - 15' W. Pine

Sept 12, 1931 G. F. DeLaMater
 Mon: Found Gas Pipe no trace of Gov' B's
 Wit: Cor of fence N56°W 48.2'
 Cor. of fence S44°E 44.2'
 Gas pipe East 33.2

L.1, P37 LCRC C. E. Ostling, RLS
 March 28, 1972
 Mon - Fd. 2" Pipe
 Wit: Fence cor. N56°W 48.2'
 Fence cor. S44°E 44.2
 Gas pipe East 33.2

MDOT FILES surveyor unknow date unknow
 Mon: 1 1/2" Pipe raised with boat spike 1' East of centerline of M-18
 Wit: 19" Oak N50°W 40.66'(DNR) 5" Poplar S40°E 64.10
 38" Oak S80°E 56.86' 18" Oak N50°E 102.18

DNR June 26, 1995 C. Roser, P.S.
 Mon - Fd. 5/8 rebar in center of road West and N-S road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner monument and accessories noted above were obliterated by recent road construction. Position reestablished from ties to control points provided by DNR. Set Standard Roscommon County monument at location established in previous survey and accepted position as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Roscommon County Monument.
 Wit: Set nail and tag 4' above ground on South side 12" Poplar S80°E 34.14 feet
 Set nail and tag 3' above ground in East side 8" White Oak S33°E 44.40 feet
 Set nail and tag South side 6" White Oak S46W 72.52 feet
 Set nail and tag South side 12" Red Oak N75°W 114.76 feet

RUSCOMMON COUNTY
PEER GROUP APPROVAL
 DATE April 19, 1999

Marvin E. Myers
 Marvin E. Myers, P.S.
 County Surveyor

Signed by _____
 Surveyor's Michigan License No. 31600



Date MAY 09, 1999