

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

6 MAY 99 2:09 P.M.

For corners in

Roscommon
 (County)

Located In:

Corner Code #

- 1. Public Land Survey T 24N R 2W
 T 24N R 3W
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

A-6
M-6

ROBERT W. SMITH
 REGISTER OF DEEDS

To be filed in Liber 3 of Land Corners
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		6		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1838
 John Brink D.S.
 Mon. - Post
 Wit: 10' S. Pine N23°W 13 links
 10' S. Pine N32 1/2°W 20 links

Roscommon County records, (Liber 2, Page 516
 Mon: 3/4" Iron bolt
 Wit: 10" Oak S73°W 41.70'
 13" Oak N43°W 54.69'
 14" Oak Due East 34.14'

DNR June 26, 1995 C. Roser, P.S.
 Mon - 1/2" Rebar in center of gravel road
 Wit: none given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 18" Iron Bolt of record in the centerline of Wheeler Road N & S.
 Found DNR location marker post East 32.7' Found dead 14" Oak East 34.14'
 Found 13" Oak stump N43°W 54.69' Found 10" Oak stump S73°W 41.70'
 Found nail & DNR reference tag in 8" White Oak S51°W 61.62' Found nail & DNR reference tag in 12" White Oak N67°E 38.60'
 Found nail & DNR tag in 12" Black Oak N53°W 38.41'
 Accepted 3/4" Iron Bolt as the best available evidence of the position of the Original Corner. Replaced Bolt with Standard Roscommon County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Roscommon County corner.
 Wit: Nail & DNR reference tag in 8" White Oak S51°W 61.62' Nail & DNR reference tag in 12" White Oak N67°E 38.60'
 Nail & DNR tag in 12" Black Oak N53°W 38.41' Set Carsonite Post 33.0' West

ROSCOMMON COUNTY
PEER GROUP APPROVAL
 DATE April 19, 1999

Marvin E. Myers
 Marvin E. Myers, P.S.
 County Surveyor



Signed by *[Signature]*
 Surveyor's Michigan License No. 31600

Date April 24, 1999