

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
2. Property Controlling in Section	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S <u>25</u> T <u>24N</u> R <u>3W</u>	<u>6</u>
	S <u>25</u> T <u>24N</u> R <u>3W</u>	<u>7</u>
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on August 06, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

6 - This position was not established during the original government survey.

7 - This position was not established during the original government survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6 - Found and accepted a 1/2" iron rod with G. Henning, RLS #2240 cap for the Southwest Corner of the Northeast Quarter of the Northeast Quarter of Section 25. This position fits standard BLM instructions for subdivision of a section.

7 - Established the Southeast Corner of the Northeast Quarter of the Northeast Quarter of Section 25 per standard BLM instructions for subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6 - Found 1/2" iron rod. Set a 1" x 32" iron pipe with PS cap over iron rod and set carsonite marker post.

Witness: Set nail in 6" Maple S 40° W 43.58'
 Set nail in 4" Maple N 54° W 16.71'
 Set nail in 10" Oak S 67° E 40.45'
 Set nail in 10" Oak N 73° E 52.68'
 Carsonite post set North 1'

7 - Set 5/8" x 8" rerod in pavement and set carsonite marker post.

Witness: Set nail in 12" Oak N 73° E 69.74'
 Set nail in 10" Oak S 37° E 67.72'
 Telephone pedestal N 79° W 44.08'
 Centerline of north-south road East 5.0'
 Carsonite post set West 33'

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 8-18-98

