

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 NR. 4 W. 1

-----Roscommon----- COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 31 & 32-----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap-----

WITNESSES TO CORNER 6" Cedar - S 65 W - 10 Links-----

10" Cedar - S 72 E - 36 Links-----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. We found two line trees, both in good condition, on this mile; one at 30 chs. and one at 50 chs.. We placed the 1/4 corner in line, and at proportionate distances between these line trees.

Corner was placed and witnessed March 17, 1952.

SURVEYORS SEAL

SIGNED Sean C. DePinto DATE 4/15/52  
REGISTERED LAND SURVEYOR