

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24. NR. 4. W. .

Roscommon COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 28, 29, 32, 33

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER 5" Cedar - N 36 W - 27 Links

10" Cedar - S 70 W - 67 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. There were several possible B.T. stumps, but I was unable to make positive identification, and established the corner by measurement.

Corner was placed and witnessed April 4, 1952.

SURVEYORS SEAL

SIGNED Sean C. DeLaRosa DATE 4/15/52
REGISTERED LAND SURVEYOR