

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T 24 N 10 R 4 W	E-1; F-1; G-1
2. PROPERTY CONTROLLING IN SECTION	N. S. E. W.	E. W.
3. MISCELLANEOUS PROPERTY IN SECTION	N. S. E. W.	E. W.
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 16, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law.

A. Description of original monument and accessories and of subsequent restoration

B. Description of corner evidence found and of method applied in restoring or re-establishing corner.


- 1 Found 1 1/2" pipe in concrete as established in previous survey by M. Schaaf, probably in 1940's.
- 1 Found 2" pipe at corner as established in previous survey by M. Schaaf, R.L.S.
- 1 Set corner on line and equidistant over 1/2 and section corners west. Unable to recover previous corner which likely was destroyed in road construction.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

E-1	F-1	G-1
Set DNR Monument	Left 2" pipe in place	Set DNR Monument
12" R. Pine S25°E 59.84	8" R. Pine N51°E 190.0	14" R. Pine N73°E 28.55
14" R. Pine S70°E 68.76	7" W. Oak N71°W 158.26	12" R. Pine N33°E 41.85
Cedar Post South 15'	Cedar Post SW 30'	Cedar Post South 14'

SIGNED BY: Kenneth J. Ostling
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068
 FOR STATE AND UNITED STATES AGENCIES.

DATE 12/22/79



SIGNED BY _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____
 DATE _____
(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ROSCOMMON COUNTY