

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>4W</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

8 JUN 99 3:50 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, DS
Mon - Post
Wit: 10" B. Oak N86°W 10 lks.
10" W. Oak N36°E 20 lks.

Marcus Schaaf 1940's
Mon: Iron Set

LCRC L1 P 199 Missaukee Co. Records
Sept 17, 1974 Herbert L. Fluharty #18223

G.L.O. - Aug 1852 Geo. H. Cannon, DS
Mon - Post
Wit: None given

Mon - 1 1/2" pipe
Wit: 14" Oak S72°W 59.85
15" Oak S44°E 58.00
8" R. Pine N28°E 69.75


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Schaaf 1 1/2" pipe in concrete. Found 18" Norway N35°E 69.64
Accepted pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Corner 0.5' below surface.
Wit: Nail E. side 18" Norway N35°E 69.64
Carsonite Post N67°E 46.26
Nail S. side 16" Twin Maple S55°E 74.84
Nail N. side 7" B. Oak S76°W 66.86

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE April 19, 1999
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

SURVEY &
RECORDATION
MAR 01 2000
SECTION

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date June 2, 1999

LIBER 3 PAGE 600