

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
RUSCOMMON COUNTY
RECORDED

8 JUN 99 3:50 P.M.

For corners in

Roscommon
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 24N R 4W B-1
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O - 1839 John Brink, D.S. Marcus Schaaf 1940's
- Mon - Post Mon - Iron Set
- Wit: 10' W. Oak N56°E 46 lks.
- 11' Yellow Pine N48°W 35 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Schaaf 1 1/2" pipe in concrete. Accepted pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon: Standard Crawford County Monument.
- Wit: West edge of Carsonite Post N52°E 19.50
- Nail & tag SE side 4" Maple N61°E 20.27
- Nail & tag SW side 5" W. Pine S28°E 48.65
- Nail & tag SW side 4" Maple (clump) N46°W 20.36

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

RUSCOMMON COUNTY
PEER GROUP APPROVAL

DATE April 19, 1999

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by _____
Surveyor's Michigan License No. 31600

Date June 27, 1999

SURVEY &
RECORDATION

MAR 01 2000

SECTION

LIBER 3 PAGE 601