

3682

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

28 APR 99 11:50 A.M.

For corners in

Roscommon
(County)

Located In:

Corner Code #

1. Public Land Survey

T 24N R 4W D-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property In Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1852
Addison P. Brewer D.S.
Mon. - Post
8" Y. Pine N22°E 14 lks.
13" Y. Pine S21°W 13 lks

Schaaf
June 1945
Mon: iron set by proportional measure.
Wit: Fire lane North.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron (stove leg in concrete) in centerline of fire lane North and 10" North of the centerline of Robinson Lake Road East & West. Accepted Iron as a careful and faithful establishment of the position of the Corner. Replaced with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Roscommon County Corner 0.4' below surface.
Wit: Set nail & tag in 12" Twin Oak N77°E 109.67'
Set nail & tag in 12" White Pine S55°E 81.87'
Set nail & tag in 38" Oak S04°W 77.86'
Set nail & tag in 4" White Pine 61.57'
Set Carsonite Post N45°E 40'±

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE April 19, 1999

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*

Surveyor's Michigan License No. 31600

Date April 23, 1999

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													