

5045

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in

8 JUN 99 3:51 P.M.

Roscommon  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 24N R 4W      E-1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2		1	
3													
4	7			6		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O - 1839 John Brink, D.S.      Marcus Schaaf 1940's  
Mon - Post      Mon - Iron Set
- Wit: 8" Pitch Pine N80°E 16 lks.  
7" Pitch Pine N81°W 26 lks.
- L1, P ? LCRC K. Ostling, RLS Dec 1979  
Mon - Found Schaaf 1 1/2" Pipe Set DNR Monument
- GLO - August 1852 Addison P. Brewer, D.S.      Wit: 12" R. Pine S25°E 59.84  
Mon - Post      14" R. Pine S70°E 68.76  
Wit: 8" S. Pine S25°E 10 lks.      Cedar Post South 15.00  
8" S. Pine S35°W 15 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found DNR Monument 0.3 below surface in fire lane N-S, & E-W; found DNR post South; found blazed 22" R. Pine S25°E 59.84; found blazed 11" J. Pine N65°E 69.06; found blazed 22" R. Pine S70°E 68.76  
Accepted DNR Monument as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon: DNR monument left in place
- Wit: Nail & Tag in 22" Norway S22°E 60.26
- Nail & Tag in 11" J. Pine N65°E 69.06
- Nail & Tag in 6" J. Pine N53°W 60.70
- Carsonite Post N46°E 38.48

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE April 19, 1999  
*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date June 3, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

LIBER 3 PAGE 604

SURVEY &  
RECORDATION  
MAR 11 2000  
SECTION