

3684

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in

28 APR 99 11:50 A.M.

<u>Roscommon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>4W</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1852  
Addison P. Brewer D.S.  
Mon. - Post  
18" Y. Pine N70W 59 lks.  
8" W. Pine S61°E 7 lks

Marcus Schaaf  
June 1945  
Mon: Intersected 1/4 corner 16 & 21 in center of fire lane north and 3 links north of county road E & W.  
Wit: Found NW BT hole  
18" Y Pine stump N37°W 51 1/2 links  
22" Y. Pine stump S17°E 223 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner falls in cut section of East-West Road (Robinson Lake Rd.). Found Schaaf's 22" Yellow Pine stump (S17°E 223 links) with the blaze still visible. Reset corner from Schaaf witness and checked chainage from the West (E-7) Corner falls in the centerline of the fire lane North and 8' North of Centerline of Robinson Lake Rd. East & West. Accepted position as a perpetuation of the Original Government Corner and set Standard Roscommon County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Roscommon County Monument 0.5' deep in centerline of firelane North and 8' North of centerline of East-West road.  
Wit: Set nail & tag 10" Red Pine N13°E 129.41'  
Set nail & tag 14" Red Pine N72°E 54.86'  
Set nail & tag 8" Twin Cherry S50°E 76.94'  
Set nail & tag 24" Twin Oak S02°W 95.38'  
Set Carsonite Post N45°E 35'±

ROSCOMMON COUNTY  
PEER GROUP APPROVAL

DATE Apr 19, 1999

*Marvin E. Myers*

Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date Apr 23, 1999