

5092

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Roscommon
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 24N R 4W H - 1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

To be filed in liber 3 of Land Corners

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

14 AUG 95 3:48 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

COMMISSION

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on July 27, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-A.P. Brewer Oct. 1852 MDOT Lyle Schmalgried Sept. 5, 1958 L.l, pg.83 K. Ostling Dec. 20, 1979
 Mon-Post Mon-4" Gas Pipe with a squared wood Mon-2 1/2" Pipe
 WIT: 7" Tamarac N45°E 13 lks. Hub laying down and scribed 1/2 WIT: 10" Spruce N32°W 18.48' 8" Cedar S11°E 22.40' 10" Spruce N38°W 17.90'
 10" Cedar N23°W 16 lks. WIT: 8" Cedar S10°W 21.90'
 MICHIGAN CENTRAL PARK L.1, pg.33 9" Cedar S11°E 22.40'
 A.E. Newman May 17, 1902 8" Spruce N29°E 23.08'
 Mon-Heavy Cedar Post From K. Ostling replat 1979
 DNR Schaaf
 Mon-2 1/2" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found 2 1/2" ID Pipe 2.5' above ground
 WIT: Fd. MSHD wit. Tag & Nail E. side 9" Cedar S13°W 22.52'
 Fd. 14" Stump N35°W 17.80'
 Fd. 2 1/2" DNR Post S55°E 2.42'

ROSCOMMON COUNTY
 PEER GROUP APPROVAL
 DATE Aug 8th 1995

Marvin E. Myers
 Marv E. Myers, P.S.
 County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set Std. Roscommon County Mon.
 WIT: Fd. MSHD wit. Tag & Nail E. side 9" Cedar S13°W 22.52'
 Set Carsonite Post S82°E 2.05'
 Set Nail N. side 5" Balsam N78°W 11.85'
 Set Nail N. side 9" Cedar S82°E 9.70'
 Set Nail E. side 3" Balsame N13°E 9.45'
 Set Nail NW side 3" Spruce S37°W 6.33'



Signed by Marvin E. Myers Date Aug 9th 1995

Surveyor's Michigan License No. 31600