

5094

JAN 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

14 AUG 95 3:49 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in  
Roscommon  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 24N R 4W H - 7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

MONUMENTATION

to be filed in liber 3 of Land Corner  
Register of Deeds Stamp & File Number

APR 05 1996

COMMISSION

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on July 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-A.P. Brewer Oct. 1852 C.E. Ostling Aug. 29, 1968 L.288, pg.238 G.D. Henning
- Mon-Set Post Mon-3/4" Pipe Mon-Unknown
- WIT: 16" W.Pine N55°E 44 lks. ARROWHEAD HILLS L.6, pg. 41 WIT: None Given
- 16" Y.Pine S38°W 36 lks. C.E. Ostling Sept. 4, 1969
- R.T. Ostling Oct. 15, 1946 Mon-3/4" Pipe
- Mon-2" Iron Pipe L.2, pg.554
- MDOT Lyle Schalgried Sept. 3, 1958 Mon-Unknown
- Mon-Fd. 1/2" Gas Pipe WIT: Cor. is 653.87'
- WIT: 11" Oak N41°W 30.80' East of NB C
- 11" Oak S69°W 26.87'
- 20" T.Oak N62°E 27.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 47" Pipe with 6" x 12" x 12" square concrete (possible Marcus Schaff DNR, Surveyor, monument). Replaced with standard Roscommon County Monuemnt. Section subdivision by G.D. Henning compares reasonably well with current retracement survey. See Book 16, T24N, R4W County Records.

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE AUG 8th, 1995

Marvin E. Myers  
Marvin E. Myers, P.S.  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-Std. Roscommon County Monument
- WIT: Fd. Spike in West face 8" W.Oak S30°E 10.61'
- Fd. Spike 12" W.Oak N41°W 30.80'
- Fd. Spike 16" Tw.R.Oak N62°E 27.15'
- Fd. Spike North face 4" Norway S88°W 43.32'
- Carsonite Post North 1.0'±



Signed by Marvin E. Myers

Date August 9th, 1995

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 246