

5093

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)

Located In:

Corner Code #

- 1. Public Land Survey T 24N R 4W J - 8
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

APR 05 1996

COMMISSION

To be filed in liber 3 of Land Corners

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

14 AUG 95 3:49 P.M.
Register of Deeds Stamp & File Number

ROBERT W. SMITH

REGISTER OF DEEDS

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on July 27, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.D. Henning Oct. 7, 1954
 Mon-Not given
 WIT: Dist. to J-9 2619.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar 1.85' NE of computed position
 Found plat monument SW 41.07' from computed position
 Accepted 1/2" bar as a careful and faithful establishment of the position of the corner

ROSCOMMON COUNTY
 PEER GROUP APPROVAL
 DATE AUG 8th 1995

Marvin E. Myers
 Marvin E. Myers, P.S.
 County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Replaced 1/2" bar with std. Roscommon County Monument
 WIT: Plat mon. SE Lot 356 HILLCREST S56°40'00"W 41.07'
 Plat mon. NW Lot 356 HILLCREST N20°34'15"W 86.42'
 J-8 to K-8 = S89°16'48"E 2607.55'
 J-8 to I-8 = N89°15'04"W 2618.40'
 J-8 to J-7 = N01°45'19"E 2615.64'
 J-8 to J-9 = S01°40'45"W 2624.27'
 Carsonite Post North 2.00'
 Polebarn Nail E. face 7" Maple (with old blaze at 22.70') A266° 23.15'
 Polebarn Nail N. face 7" Poplar A2121° 12.71'
 Polebarn Nail NE face 12" R.Oak A2229° 10.30'
 Fd. 6" Maple with old balze A2292° 5.20'±
 Polebarn Nail NW face 9" R.Oak A2303° 10.46'



Signed by *Marvin E. Myers*

Date AUG 11, 1995

Surveyor's Michigan License No. 31600

1.000 2 P... 1111