

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in

<u>Roscommon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>22NR 4W</u>	<u>J-10</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

28 APR 99 11:48 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on November 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

LORC L. 1, P. 83-84  
April 1973 L. L. Cavanagh, P.S. #17614  
Mon - Found 1/2" Bar  
Wit: 10" Oak S60°E 47.75  
4" Oak N85°W 22.15  
8" Oak North 47.9

L2, P277 LORC  
Mon - 1/2" Bar  
Wit: 10" Oak S60°E 47.75  
4" Oak N85°W 22.15  
8" Oak North 47.9

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x 18" bar at intersection of 1/4 lines. 1 foot south of fence post. Accepted 1/2" bar as a careful and faithful establishment of the position of the corner. Replaced 1/2" bar with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument.  
Wit: Set spike in 10" Blazed Oak N25°W 27.49  
Set spike East side 4" Poplar S21°W 26.93  
Set spike in North side 6" Maple N64°E 24.13  
Set spike in South side 10" Poplar N79°W 8.84

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE April 19, 1999

Marvin E. Myers  
Marvin E. Myers, P.S.  
County Surveyor



Signed by Marvin E. Myers Date April 23, 1999  
Surveyor's Michigan License No. 31600