

ROSCOMMON COUNTY REMONUMENTATION

9228 FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE

DEC 28 10 27 AM '93

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 4W	K - 9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert J. ...
REGISTER OF DEEDS

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO - Aug. 1852 A.Brewer
Mon. - Post
WIT: 12" S.Pine N15°W 115 lks.
12" Y.Pine S44°E 83 lks.
Old Post N12½°E 848 lks.
- Reg. of Deeds
Mon. - ½" Bar
WIT: 10" B.Oak N05°30'E 62.00'
24" B.Oak N60°E 61.10'
- L.271, pg.331 Aug. 1972 L.Cavanagh
Mon. - Fd. ½" Bar
L.332, pg.575 July 1976 L.Cavanagh
Mon. - unknown
WIT: 8" B.Oak N05°30'E 62.00'
10" B.Oak S29°W 28.70'
- L.1, pg.115 LCRC June 1978 F.Arleth
Mon. - ½" Bar
WIT: 10" B.Oak N05°30'E 62.00'
24" B.Oak N60°E 61.10'
- L.1, pg.115 LCRC April 1978 L.Cavanagh
Mon. - ½" Bar
WIT: 10" Oak N45°W 69.95'
24" B.Oak N50°E 60.00'
Spike in P.P. S45°W 40.80'
- L.347, pg.175 June 1978 F.Arleth
Mon. - Fd. ½" Bar
WIT: 10" B.Oak N05°30'E 62.00'
24" B.Oak N60°E 61.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found ½" x 18" Bar over ½" Bar drove 2nd Bar down. Verified position by measurement to accessories of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- Mon. - Std. Roscommon County Monument
- WIT: Fd. nail in W. side 30" Tw.Oak North 19.70'
- Fd. nail in NW side 27" Oak N76°E 61.05'
- Fd. nail in E. side 15" Oak South 43.28'
- Fd. nail in SE side Power Pole S55°W 40.83'
- Fd. blaze 12" B.Oak N05°30'E 62.00'
- Fd. blaze 12" B.Oak N45°W 65.95'
- Fd. blaze 27" B.Oak N50°E 60.00'
- Q E - W road South 7'±



Signed by Marvin E. Myers Date December 21, 1993

Surveyor's Michigan License No. 31600

Date December 14, 1993 Peer Group Approved