

9231 FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

DEC 28 10 27 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>4W</u>	<u>K - 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert E. Myers
REGISTERED SURVEYOR

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-21-93

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Aug. 1852 A. Brewer Mon. - Post Wit: 12" Aspen N43°E 20 lks. 10" Aspen S76°W 24 lks.	Sept 1932 DeLaMater Mon- Not given Wit- Not given	Old G. Henning Work Map date unknown Mon- not given Wit- not given
---	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x24" bar verified position by measurement to accessories and corners of record locations fits GLO call for swamp East and is accepted as the best available evidence for the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon- Set Standard Roscommon County Monument
Wit- Nail & tag NW side 6" Maple S48°W 28.66
Nail & tag N. side 7" Maple N82°E 16.17
Nail & tag NW side 13" Maple N11°E 40.08
Nail & tag SW side 9" Oak N58°W 39.97
Set Carsonite Post 1.35 East



Signed by *Marvin E. Myers* Date Dec 27, 1993

Surveyor's Michigan License No. 31600

Date Dec 21, 1993 Peer Group Approved