

11764

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

30 NOV 1999 4:15:19 PM

For corners in  
Roscommon

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in Roscommon (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>24N</u> R <u>4W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on June 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-1852	Robert T. Ostling RLS	Frank J. Arleth, P.S. 21266
G.H. Cannon, DS	Map of alignment survey	Unrecord Alignment Survey, 5-29-66
Mon- Post	for Roscommon Co. Road	Mon - Found 2" pipe
Wit: Birch N23 1/2°E 26 lks.	Commission July 20, 1951	Wit: Place bar & Cap #21266
7" B. Oak N51 1/2°W 34 lks.	Mon - Found 2" pipe in	East 28.10
	concrete base set from	Place bar & cap #21266
	remains of US BT's	North 20.00
	Wit: Spike in 14" R. Oak N37°W 55.96	
	Spike in 8" Oak S 1/2°E 37.60	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" pipe of record in South edge of grave (Forest Ave) and in the centerline of fire lane North. Found bar & cap #21266 East 28.10. Found bar & cap #21266 North 20.0  
Accepted pipe as a Perpetuation of the Original Government Corner. Replaced pipe with Standard County Monument.

RUSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Sept 10, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard County Monument.  
Wit: Set nail in NW side 20" White Pine N35°W 33.76  
Set nail in N. side 16" Black Oak N60°E 80.44  
Set nail in NE side 18" Ash S14°E 19.15  
Set nail in E. side 26" White Pine S46°W 50.67  
Set Carsonite post 30' North



Signed by *Marvin E. Myers* Date Nov 29, 1999

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

RECORDED

MAR 01 2000

LIBER 3 PAGE 625

SECTION

9-