

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

FEB 18 1994
9229

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 28 10 27 AM '93

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 4W	L - 10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert J. Myers
REGISTERED SURVEYOR

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Reg. of Deeds	L.315, pg.129 Mar. 1976 F.Arleth	L.1, pg.149 LCRC Mar. 1976 F.Arleth
Mon. - 1" Iron	Mon. - 1" Bar	Mon. - 1" Sq. Iron
WIT: 8" B.Oak N37°W 66.80'	WIT: 8" B.Oak N37°W 66.80'	WIT: 8" B.Oak N37°W 66.80'
16" B.Oak S69°W 69.60'	16" B.Oak S69°W 69.60'	16" B.Oak S69°W 69.60'
½" Bar West 33.00'		½" Bar West 33.00'
L.284 pg. 324 Nov. 1973 L.Cavanagh	L.289 Pg.676 April 1974 C.Ostling	May 1991 F.Arleth
Mon. - Shown not described	Mon. - 1" Sq. Iron	Mon. - ½" Bar
	WIT: 8" B.Oak N37°W 66.80'	WIT: 8" B.Oak N37°W 66.80'
L. 306 pg.81 June 1975 R.Higgins	16" B.Oak S69°W 69.60'	16" B.Oak S69°W 69.60'
Mon. - Shown not described	½" Bar West 33.00'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" x 12" Square head spike in centerline of North - South County Road #202. Set standard monument in new pavement box and accepted as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Std. 21" Roscommon County Monument
WIT: Fd. nail in bottle cap in NE side of Power Pole S32°E 54.37'
Fd. old blaze SE side 12" Oak N37°W 66.80'
Fd. old blaze NE side 18" B.Oak S69°W 69.40'
Nail & tag NE side 5" R.Pine (Norway) N32°W 57.08'
Nail & tag SE side 20" Oak S66°W 44.43'
Nail & tag SE side 17" Oake N52°E 76.84'
W½ corner N89°32'42"W 2640.08
E½ corner S89°33'23"E 2642.48
N½ corner N01°30'26"E 2637.18
S½ corner S01°30'26"W 2642.14



Signed by Marvin E. Myers

Date Dec 21, 1993

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

Date December 14, 1993 Peer Group Approved

LIBER 3 PAGE 55