

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

9227 FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 28 10 27 AM '93

For corners in COMMISSION

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>4W</u>	<u>L - 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Aug. 1852 A. Brewer Mon. - Post WIT: 16" Y.Pine S04°W 30 lks. 8" S.Pine N08°E 35 lks. Enter Swamp North 187 lks.	L.1, pg. 149 LCRC F.Arleth Mar. 1976 Mon. - 3/4" Bar WIT: 18" N.Pine N30°E 70.70' 6" J.Pine S61°E 31.30' 1/2" Bar N89°26'W 33.00'	L.315 pg. 129 Mar. 1976 F.Arleth Mon. - 3/4" Bar WIT: 16" W.Pine N30°E 70.70' 6" J.Pine S61°E 31.30'
L.2 pg. 575 Reg. of Deeds Mon. - 1/2" Iron Bar 110'± South of Rd. 104 WIT: 18" Norway N30°E 70.70' 6" J.Pine S61°E 31.10'	L.289, pg.676 April 1974 C.Ostling Mon. - 3/4" Iron WIT: 18" N.Pine N30±E 70.70' 6" J.Pine S61°E 31.30' 1/2" Iron Bar N89°26'W 33.00'	May 1991 F.Arleth Mon. - 1/2" Bar WIT: 18" N.Pine N30°E 70.70' 6" J.Pine S61°E 31.30'
Sept. 1932 G.Delmater Mon. - 1/2" Bar WIT: 15" S.Pine N58°W 9.80' 15" S.Pine N43 1/2°E 44.50' (point believed to be true cor. is N84°W 18.00') (Dist. to sec. Cor. N89°15'W 2676'±)		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found 5" Spike over 1/2" x 18" copper pipe with 1 1/2" Brass cap over 1/2" x 18" bar on centerline extension of County Road #202 309'± South of centerline of County Road #104 and accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Std. Roscommon County Monument
WIT: Fd. 1/2" Bar N84°W 33.01
Nail & Tag S. side 12" B.Oak West 39.25'
Nail & Tag NW side 18" B.OAK N50°E 81.55'
Nail & Tag NE side 9" Balsam Fir N43°W 47.55'
Nail & Tag SW side 7" Poplar S44°E 62.38'



Signed by Marvin E. Myers

Date December 21, 1993

Surveyor's Michigan License No. 31600

Date December 14, 1993

Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER

3 PAGE 53