

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Roscommon
(County)

Located in:

Corner Code #

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

13 OCT 97 12:38 P.M.

ROBERT W. SMITH
 REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>24N</u>	R	<u>4W</u>	<u>L - 13</u>
	T	<u>23N</u>	R	<u>4W</u>	<u>A - 1</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on August 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - J. Brink, D.S. June 1838	L.L. Cavanagh, P.S. #17614 Jan. 4, 1995
Mon. - Post	Mon. - Not given
WIT: 10" W.Oak N82½°E 41 lks.	WIT: 10" Black Oak N70°E 29.43'
12" W.Pine N55°W 39 lks.	6" Black Oak S27°E 44.83'
	15" Black Oak S60°W 33.32'
	14" Black Oak N58°W 31.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" x 18" rebar & cap verified position by measurement to LLC accessories and accepted as a careful and faithful reestablishment of the position of the corner.
 Replaced ½" bar & cap with standard Roscommon County monument

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

**ROSCOMMON COUNTY
 PEER GROUP APPROVAL
 DATE Aug 11, 1997**

Marvin E. Myers
**Marvin E. Myers, P.S.
 County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Roscommon County monument
 WIT: 10" Black Oak N70°E 29.43'
 6" Black Oak S27°E 44.83'
 15" Black Oak S60°W 33.32'
 14" Black Oak N58°W 31.55'



Signed by *Marvin E. Myers*
 Surveyor's Michigan License No. 31600

Date Sept 12, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LIBER 3 PAGE 423