

ROSCOMMON COUNTY REMONUMENTATION

9226

FEB 18 1984

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 28 10 27 AM '93

For corners in ROSCOMMON

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>4W</u>	<u>M - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert L. Cavanagh
REGISTERED SURVEYOR

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-14-93**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - April 1839 J.Brinks Mon. - Post WIT: 8" Y.Pine S14½°W 18 lks. 9" Aspen N24°W 25 lks.	Reg. of Deeds Mon. - ½" Bar WIT: 12" W.Oak S70°E 36.60' 14" B.Oak N40°E 52.62' 12" W.Oak N50°W 61.50'	L.344, pg.223 April 1978 L.Cavanagh Mon. ½" Bar WIT: 12" W.Oak S70°E 36.60' 14" B.Oak N40°E 52.62' 12" W.Oak N50°W 61.50'
GLO - June 1852 W. Burt Mon. - Fd. Post WIT: 10" Y.Pine S79°E 17 lks.	L.304, pg.219 May 1975 L.Cavanagh Mon. - ½" Bar	Jan. 1991 L.Cavanagh Mon. - ½" Bar WIT: 7" R.Oak N34°W 41.35' 15" R.Oak N38°E 52.50' 12" W.Oak S79°E 36.50'
Dec. 1924 G.Delmater Mon. - Iron @ Cor. Fd. Post WIT: 12" Y.Pine West 57.50'	Nov. 10, 1945 G.Henning Mon. - ½" Ba WIT: 10" W.Oak N27°W 62.00' 6" B.Oak N37°E 53.00'	
Nov. 1945 G.Delmater same as above	12" N.Pine S21°E 93.70'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found ½" x 30" Bar verified position by measurement to accessories of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Std. 21" x 2" Roscommon County Monument
WIT: Spike NW side 18" R.Oak N42°E 53.12'
Spike N side 12" W.Oak S69°E 36.61'
Nail & tag SE face 9" Maple S52°W 12.02'
Spike NE side 9" R.Oak N31°W 41.57'
2" Well point N88°W 22.28'



Signed by *Marvin E. Myers*

Date December 21, 1993

Surveyor's Michigan License No. 31600

Date December 14, 1993

Peer Group Approved

LIBER

3 PAGE 52