

9223
FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 28 10 27 AM '93

For corners in **COMMISSION**

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 4W	M - 11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert [Signature]
REGISTER OF DEEDS

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-1993**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on Dec 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|--|---|---|
| GLO - April 1839 J.Brink
Mon. - Post
WIT: 8" W.Oak S09°W 39 lks.
7" P.Pine N05½°W 22 lks. | L289, pg.676 April 1974 C.Ostling
Mon. - ½" Bar
WIT: 8" B.Oak Stump N40°W 60.50'
6" B.Oak Stump N52°E 70.40'
½" Bar N44°57'W 46.30' | L.1, pg.149 LCRC F.Arleth
Mon. - ½" Bar
WIT: 8" B.Oak N40°W 60.50'
6" B.Oak N52°E 90.40'
½" Bar N94°57'W 46.30' |
| Reg. of Deeds
Mon. - ½" Bar
WIT: 8" B.Oak N40°W 60.50'
6" B.Oak N52°E 70.40'
½" Bar N45°W 46.30' | L.315, pg.129 Mar. 1976 F.Arleth
Mon. - Pd. ½" Bar
WIT: 8" B.Oak Stump N40°W 60.50'
6" B.Oak Stump N52°E 70.40' | May 1991 F.Arleth
Mon. - ½" Bar
WIT: 8" B.Oak N34°W 55.80'
16" B.Oak S69°W 69.60' |
| Nov. 1947 G.Henning | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found ½" x 30" bar 8'± South of Center of E-W Road verified location by measurement to accessories and corners of record and accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon- replaced ½" x 30" bar with Std. County Monument.
Wit- Set Std nail & tag in SW side 9" B. Oak N47°W 87.00
Found ½" bar and cap #12026 N40°W 46.25
Found Concrete monument N06°E 41.02
Found ½" bar in center line of E-W road N06°E 7.97
Nail & tage in NE side Power Pole S42°E 50.57
Found spike NW side 11" B. Oak S44°W 99.17



Signed by Marvin E. Myers Date Dec 18, 1993
Surveyor's Michigan License No. 31600

Date Dec 7, 1993 Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983