

SURVEY & REMONUMENTATION

MAR 12 1999

LIBER 2085 PAGE 1403

SECTION

APPROVED BY PEER GROUP 1998 REMONUMENTATION PROGRAM  
 P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE  
 SAGINAW COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

*[Signature]*  
 For corners in

RECORDED/FILED  
 1998 OCT 13 P 2:10  
 MILDRED H. DODAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY, MI.  
*Lib 7 Page 262*  
 Register of Deeds Stamp & File Number

Saginaw Located In: Chapin Twp. Corner Code # C-13  
 (County)

- 1. Public Land Survey T 9N R 1E C-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John H. Rauser, in a field survey on July and August 19 98

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-13 Closing Township Corner, Section 5, T8N-R1E and Section 32, T9N-R1E  
 Wood post placed by Robert Clark, Jr. D.S. Feb. 27, 1831  
 S24°E 40 lks (28.40') 16" Elm  
 N28 1/2°E 52 lks (34.32') 10" Birch  
 South 58.28 chs (3846.48') Township Corner, T8 and 9N-R1W  
 Shiawassee County Survey by Lyman Mason, June 1876. Recorded in Book D, Pgs 118-119, S.C.D.R. "stake and stones". N4°55'E 215 lks (141.90') 8" Oak  
 Gratiot County Survey by Thomas H. Harrod, C.S., April 5-7, 1880. Recorded in Book C, Pg.41, G.C.R.  
 Iron bar 1"x32" long- stones- o.c.f. Walnut 14" 43.4 lks (28.64')  
 NW 110.8' DBL Butternut  
 E & W 25' stakes  
 South 58.28 chs (3846.48') to the Standard Township Corner, Section 1, T8N-R1W and Sec. 36, T9N-R1W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Closing Township Corner, Section 5, T8N-R1E and Section 32, T9N-R1E  
 Found 3/4" pipe, with occupation East and 0.66' East of the Michigan Meridian. This position fits well with the G.L.O. closing distance and the Gratiot County record (record 58.28 ch = 3846.48' measured 3847.45')  
 Calculated a true position for the closing corner on the Michigan Meridian  
 During excavation for placement of Harrison monument, found record stone on the Michigan Meridian. Removed stone and found no more evidence. The position of the stone is accepted as a careful and faithful perpetuation of the position of the original corner.  
 Approved by the Shiawassee County Remonumentation Peer Review Group, 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Closing Township Corner, Section 5, T8N-R1E and Section 32, T9N-R1E  
 Placed a standard Harrison monument 0.6' below gravel surface  
 West 13.25' Set 1/2" rod in forward slope of ditch bank  
 N20°E 113.55' Set N&T #39096 in W'y fc of 24" Walnut  
 N45°E 58.12' Set N&T #39096 in SE fc Tele. Pole  
 S88°E 32.30' North side, center of 6" steel post  
 S88°E 50.40' Set N&T #39096 in S fc PP  
 South 3847.45' Fnd Clinton County Remon. cor. @ the Standard Township Corner, Sec. 1, T8N-R1W and Sec. 36, T9N-R1W

Signed by *[Signature]*  
 Surveyor's Michigan License No. \_\_\_\_\_

