

APPROVED BY PEER GROUP 1999 REMONUMENTATION PROGRAM
P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE
SAGINAW COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 30 A 8:10
MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

For corners in

LIBER 2144 PAGE 1448

Lib 8 Page 70

Register of Deeds Stamp & File Number

Saginaw Located In: Corner Code #
(County) Chapin Twp.
1. Public Land Survey T 9N R 1E E-9
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on September 27 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-9 Section Corner, Sections 20, 21, 28, & 29, Chapin Township
1831 GLO wood post placed by Robinson Thomas, D.S.
S43W 12lks (7.92') Elm
N22E 27lks (17.82') Elm

RECORDED
MAR 10 2000

No subsequent record of restoration or perpetuation.

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 Section Corner, Sections 20, 21, 28, & 29, Chapin Township

Found no evidence of the original government accessories. Found 3/4" pipe at corner, approximately 2' South of the centerline of Ferden Road & in line with an occupied field line to the South. We found a corner card, indexed as E-9, at the Saginaw County Road Commission from 1978, which was actually for D-9. Found PK in East face of power pole to the south, but could find no record of the witness. Measured West to D-9 S88°17'33"W, 741.74 feet (GLO = 11.20 chains, 739.2'), measured East to F-9 2642.33' (GLO = 2633.07'). We recommend that the found 3/4" pipe be accepted as the best available evidence of the position of the original government corner and be replaced with a standard Saginaw County 5/8" re-rod with brass cap and place in a monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 Section Corner, Sections 20, 21, 28, & 29, Chapin Township

Set 5/8" re-rod with standard Saginaw County brass cap stamped "E-9 1999 39096" and monument box.

N04W 25.97' Top center phone riser
South 57.72' Set PK nail/tag #39096 in W fc PP
N52E 23.77' Set 1/2" rod/flag at top of ditch bank
S66W 26.29' Set 1/2" rod/flag at top of ditch bank

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date _____

