

RECORDED/FILED

APPROVED BY PEER GROUP 1999 REMONUMENTATION PROGRAM  
P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE  
SAGINAW COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 30 A 8:10

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 1446

*Lib 8 Page 68*  
Register of Deeds Stamp & File Number

For corners in

Saginaw Located In: Chapin Twp. Corner Code #  
(County)

- 1. Public Land Survey T9N R1E F-9  
T R
- 2. Property Controlling S T R  
in Section S T R EF
- 3. Miscellaneous S T R  
Property in Sec. S T R

MAR 9 2000

- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_ SECTION \_\_\_\_\_

I, John H. Rauser, P.S., in a field survey on September 27 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9 1/4 Corner, Sections 21 & 28, Chapin Township

1831 GLO wood post placed by Robinson Thomas, D.S., at the split distance of 39.895 chains (2633.07')  
S23E 8lks (5.28') 6" Sugar  
N28W 15lks (9.90') 54' Hickory

No subsequent record of restoration or perpetuation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 1/4 Corner, Sections 21 & 28, Chapin Township

Found no evidence of the original government accessories. Found 1/2" re-rod bent to the South in the centerline of Ferden Road with occupied tree line to the South, no apparent occupation to the North. Found no conflicting evidence in the vicinity of this position. Measured West to E-9 2642.33 feet and East to G-9 2642.33 feet. Corner falls on line between G-9 and E-9. We recommend that the found 1/2" re-rod be accepted as a careful and faithful re-establishment of the position of the original government corner and be replace with the standard Saginaw County 5/8" re-rod with brass cap and place in a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 1/4 Corner, Sections 21 & 28, Chapin Township

Set 5/8" re-rod with standard Saginaw County brass cap stamped "F-9 1999 39096" and monument box

- S69E 32.60' Set 1/2" rod/flagging 3' S of EM @ TB
- S64W 30.29' Set 1/2" rod/flagging 3' S of EM @ TB
- N66W 29.82' Set 1/2" rod/flagging 3' N of EM @ TB
- N67E 34.08' Set 1/2" rod/flagging 3' N of EM @ TB

Signed by John H. Rauser

Date \_\_\_\_\_

Surveyor's Michigan License No. 39096

