

RECORDED/FILED

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 30 A 8:10

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

2-21 [Signature]  
For corners in

LIBER 2144 PAGE 1447

Lib 8 Page 69  
Register of Deeds Stamp & File Number

- Saginaw (County) Located In: Chapin Twp. Corner Code #
- 1. Public Land Survey T 9N R 1E F-11  
T \_\_\_ R \_\_\_
  - 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
  - 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_
  - 4. Lot No. \_\_\_ Recorded Plat \_\_\_
  - 5. Private Claims \_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, John H. Rauser, P.S., in a field survey on September 24 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-11 1/4 Corner, Sections 28, & 33, Chapin Township

1831 GLO wood post placed by Robinson Thomas, D.S. set a split distance of 40 chains (2640')  
N46W 24lks (15.84') 14" Beech  
S40E 47lks 31.02' 6" Beech

No subsequent record of restoration or perpetuation

SEP 29 2000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 1/4 Corner, Sections 28, & 33, Chapin Township

Found no evidence of the original government accessories. Found 1" iron bar in the centerline of Kramer Road in line with a fence/tree line occupation to the North. Found no existing witnesses or conflicting evidence in the vicinity of this position. Measured West to the found closing corner at D-11 3456.59' (GLO = 3445.20'), measured East to G-11 2656.08' (GLO = 2640'). The prorated distance to E-11 calculates to be 2648.73' (GLO = 2640'). The position of the found 1" iron bar is 3.68' from a split of the re-established E-11 and G-11 and falls 0.44' North of a line between E-11 and G-11. We recommend that the 1" iron bar be accepted as the best available evidence of the position of the original government corner and be replaced with a standard Saginaw County 5/8" re-rod with brass cap in a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 1/4 Corner, Sections 28, & 33, Chapin Township

Set 5/8" re-rod with standard Saginaw County brass cap stamped "F-11 1999 39096" and monument box.

S77E 39.84' Set 1/2" re-rod/flag on NE side of top of bank  
N68W 32.37' Set 1/2" re-rod/flag on NW side of top of bank  
N02W 25.03' Fnd 2" angle iron fence post N of Kramer Road  
S16W 164.17' Set PK/tag #39096 in E fc PP

Signed by [Signature]  
Surveyor's Michigan License No. 39096

Date

