

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

1999 SEP 30 A 8:09

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

For corners in

- | | | | | |
|---------------------------------------|----------------------------|---------------|------------|-------|
| <u>Saginaw</u>
(County) | Located In:
Chapin Twp. | Corner Code # | | |
| 1. Public Land Survey | T <u>9N</u> | R <u>1E</u> | G <u>9</u> | |
| | T _____ | R _____ | | |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 3. Miscellaneous Property In Sec. | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | | |
| 5. Private Claims _____ | | | | |

LIBER 2144 PAGE 1442

Liber 8 Page 64
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on September 20, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Section Corner, Sections 21, 22, 27, & 28, Chapin Township

1831 GLO wood post placed by Robinson Thomas, D.S.
N88E 15lks (9.9') 6" Elm
S63W 29lks (19.14') 12" Beech

1987 Rowe witness card & field note sketch, found 1/2" re-rod in CL - CL of Fenmore and Ferden Rds

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Section Corner, Sections 21, 22, 27, & 28, Chapin Township

Found no evidence of the original government corner accessories. Found bent 1/2" re-rod without cap approximately 1.5' East of the centerline of Fenmore Road and in the centerline of Ferden Road. Rod is bent to the North, held where straight in ground. Found no conflicting evidence in the vicinity of this corner. Measured South to G-10 2658.12' and West to F-9 2642.33'. We recommend that the found 5/8" re-rod be accepted as the best available evidence of the position of the original government corner and be left in place and a standard Saginaw County brass cap be attached thereto and a monument box be installed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 Section Corner, Sections 21, 22, 27, & 28, Chapin Township

Set 5/8" re-rod with standard Saginaw County brass cap stamped "G-9 39096" and monument box

S45W 29.00' Fnd PK nail/tag #11192 in top of N'y guard rail post
S50E 29.94' Fnd PK nail/tag #11192 in top of N'y guard rail post
N28E 38.6' S edge phone marker post
N61W 38.6' E edge phone marker post

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date _____

