

RECORDED/FILED

APPROVED BY PEER GROUP 1999 REMONUMENTATION PROGRAM  
P.A. 345 OF 1990  
SAGINAW COUNTY LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 30 A 8:09

MILDRED M. DUDAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

B-11 [Signature]

For corners in

Saginaw Located In: Corner Code #  
(County) Chapin Twp.

1. Public Land Survey T 9N R 1E G-12  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

LIBER 2144 PAGE 1443

Lib 8 Page 65  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John H. Rauser, P.S., in a field survey on September 27 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-12 1/4 Corner, Sections 33, & 34, Chapin Township  
1831 GLO wood post placed by Robinson Thomas, D.S.  
Beech 10" N21E 12lks (7.92')  
Beech 8" S41W 36lks (23.76')

RF  
2000  
SECTION

No subsequent record of restoration or perpetuation

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 1/4 Corner, Sections 33, & 34, Chapin Township  
Found no evidence of the original government accessories. Found 1' X 6" stone with small stones around, 3'+ below the asphalt grade, in line with occupation East & West. Measured North to G-11 = 2639.50' and 1325.4' to a fence line on trees to the East. Measured South to G-13 = 2654.28', found no occupation at the 1/8 line location. Found 12" diameter ancient corner post 26.5' East of the stone with fence (down and poor) and large mature trees on fence line running East. Spoke with elderly resident of the area who stated that the corner post has been at that position as long as he could remember. We recommend the position of the found stone be accepted as a careful and faithful perpetuation of the position of the original government corner and be left in place with the standard Saginaw County 5/8" re-rod with brass cap and monument box be place over it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 1/4 Corner, Sections 33, & 34, Chapin Township  
Left stone in place and set 5/8" re-rod with standard Saginaw County brass cap stamped "G-12 39096" and monument box over stone.  
East 61.36' Set spike w/tag #39096 in South face 28" oak  
N45E 57.10' Set spike w/tag #39096 in Southeast face 6" quad poplar  
N45W 30.73' Set 1/2" re-rod w/flagging in top of road side ditch  
S45W 24.52' Set 1/2" re-rod w/flagging in top of road side ditch  
N60W 12.76' 1/2" re-rod with ROWE traverse cap



Signed by John H. Rauser  
Surveyor's Michigan License No. 39096

Date \_\_\_\_\_